

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

23-31-6W


Company- THE TEXAS COMPANY  
Farm-S. E. Knowles Unit No. 1

SEC. 23 T. 31 R. 6W  
NE SW NE

Total Depth. 4719; PB 4699  
Comm. 12-30-54 Comp. 1-29-55  
Shot or Treated.  
Contractor. Stickle Drlg. Co.  
Issued. 4-2-55

County Harper

KANSAS



CASING:

10 3/4" 514' cem. w/550 sx. circ.  
7" 4716'

Elevation. 1403 DF

Production. 4,930,000 gas &  
30 BO

Figures Indicate Bottom of Formations.

redbed shale & shells	500
shale	514
shale & shells	830
shale, shells & salt	1050
Anhydrite	1100
shale & shells	1250
lime & shale	1860
shale & shells	1975
shale	2100
lime & shale	2315
shale & shells	2609
sand	2619
sandy shale	2672
lime & shale	2850
shale, lime & sand	3005
sandy shale	3040
lime & shale	3205
sand & shale	3220
shale	3409
sand	3470
shale & lime	3509
shale	3604
shale & shells	3648
lime	3878
lime & shale	4204
shale & chat	4245
lime	4253
lime & chert	4297
lime	4381
broken lime	4453
chalky lime	4540
lime & shale	4599
shale	4669
sand	4719
Total depth; PB 4699	
Tops:	
Severy sand	2604
Topoka	2658
Douglas	3172

Stalnaker	3396
Kansas City	3648
Base Kansas City	3882
Marmaton	3945
Cherokee	4075
Mississippi	4245
Kinderhook	4553
Chatanooga	4643
Simpson sand	4669

