

24-31-6W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
Farm- C. M. Springer No. 3

SEC. 24 T. 31 R. 6W
SW SW SW

Total Depth. 4659'
Comm. 4-13-58 Comp. 5-2-58
Shot or Treated.
Contractor. Stickle Drilg. Co.
Issued. 7-5-58

County Harper
KANSAS



CASING:
10 3/4" 505' cem w/325 sx.
7" 4659' cem w/225 sx.

Elevation. 1396' DF

Production. 226 BOPD

Figures indicate Bottom of Formations.

surface	0
shale & shells	85
sandy shale & shells	165
red bed, shale & shells	345
red bed & shells	505
shale & shells	1080
lime broken & shale	1275
lime & shale	1840
shale & lime	2980
lime & shale	3075
shale & lime	3225
lime & shale	3380
sand & shale	3470
lime & shale	3665
lime	3793
lime & shale	4005
shale & lime	4225
chert & lime	4255
lime shale & chert	4285
lime & chert	4313
lime	4350
lime & chert	4429
broken lime	4505
lime & chert	4555
lime & shale	4600
Kinderhook shale	4630
shale	4657
shale	4659

Total Depth

TOPS:

Kansas City	3624
Base Kansas City	3856
Marnaton	3921
Cherokee	4052

Mississippi Chat	4226
Mississippi Lime	4244
Kinderhook	4536
Chattanooga	4623
Simpson	4646

Perf. 4653-57'