

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

Computer Inventoried

COMPANY **PICKRELL DRILLING**

SEC. 1 T. 31 R. 7W
 LOC. C NE

FARM Pomeroy Ut

NO. 1

TOTAL DEPTH **3630'**

COMM. **6-19-67**



COMP. **6-26-67**

SHOT OR TREATED

CONTRACTOR **Gabbert-Jones**

ISSUED **10-14-67**

COUNTY **Harper**
KANSAS



CASING

20	10	
15	8 5/8" 204'	cem w/ 165 sx
12	6	
13	5	
	4 1/2" 3626'	cem w/ 125 sx

1583' KB

ELEVATION

PRODUCTION **4500 MCFGPD**

Stal sand 3525 SIT 1290 &
 SICP 1290#

0	50
50	204
204	820
820	1200
1200	1270
1270	1800
1800	1950
1950	3530
3530	3630
3630	TD

SAND
 RED BED
 RED BED AND SHALE
 SHALE
 LIME
 LIME AND SHALE
 LIME
 SHALE AND LIME
 SAND

RAN 10 JOINTS 8-5/8" CASING, SET @
 204' w/165 BAGS CEMENT.

TOPS: LOG
 Heebner 3238
 Douglas shale 3328
 Stalnaker sand 3518

RAN 112 JOINTS 4 1/2" CASING, SET @
 3626' w/125 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL
 DRILLED 50' N OF C NE 1/4 SECTION 1-31S-7W, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOW-
 LEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE,
 ON THIS 28TH DAY OF JUNE, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO
 BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED
 TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND
 PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND
 YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.