

WELL LOG

15-077-20289

20-31-7W

COMPANY Rains & Williamson Oil Co., Inc.

SEC. 20 T. 31S R. 7W

FARM Hudson Estate NO. 1

LOC. C S/2 S/2 SE/4


RIG. NO. 3

TOTAL DEPTH 4666'

COMM. 1-9-75

COMP. 2-1-75

COUNTY Harper
KANSAS



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASING

20 10
15 8-5/8" @ 276' w/225 sx common, 2% gel, ELEVATION 1515 KB
12 6 3% cc
13 5 1/2" @ 4663' w/125 sx common-18% salt, PRODUCTION Oil
3/4 of 1% CFR2.
FIGURES INDICATE BOTTOM OF FORMATIONS

Redbed & Shells	25
Redbed	260
Shale	1275
Lime	1880
Lime & Chert	1969
Lime	2015
Lime & Chert	2029
Lime	2095
Lime & Shale	2270
Shale & Lime	2675
Shale	2845
Shale & Lime	3065
Lime & Shale	3190
Shale & Lime	3320
Lime & Shale	3515
Shale & Lime	3788
Lime	3925
Shale & Lime	3950
Lime	4060
Shale & Lime	4140
Lime	4360
Chert	4553
Shale	4650
Sand	4666
<u>Rotary Total Depth</u>	<u>4666</u>

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1975

CONSERVATION DIVISION
Wichita, Kansas

