

23-31-7W


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY ANADARKO PRODUCTION CO.
 FARM Parsons "F" NO. 1

SEC. 23 T. 31 R. 7W
 LOC. C NW SE

TOTAL DEPTH 4859'
 COMM. 6-2-68 COMP. 6-17-68
 SHOT OR TREATED
 CONTRACTOR Leben Drig., Inc.
 ISSUED 7-27-68

COUNTY Harper
 KANSAS



CASING

20	10	
15	8 5/8	637' w/350 ex cem
12	6	
13	5	

ELEVATION 1515' G.L.

PRODUCTION DRY/SIMP.

FIGURES INDICATE BOTTOM OF FORMATIONS

0	30'	Sand	TOPS: SCOUT	
30	640	Red Bed	Heebner	3262
640	1190	Shale	Stalnaker	3549
1190	1225	Anhydrate	Lansing	3816
1225	1460	Shale, Lime	Mississippi	4390
1460	1700	Lime, Shale	Simpson sand	4774
1700	1880	Lime		
1880	2065	Lime, Shale		
2065	2860	Shale, Lime		
2860	3080	Lime, Shale		
3080	3464	Shale, Lime		
3464	3900	Lime, Shale		
3900	4778	Lime		
4778	4859	Sand		
		RTD - D & A		

8 5/8" New 24# Surface casing set @ 637' with 350 ex 50-50
 Posmix HA-5 plus 100 ex common - 3% HA-5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Parsons F-1 well, located @ NE SE of Section 23, Township 31 South, Range 8 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS

SS

COUNTY OF BARTON

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 19, day of June, 1968.