

5-31-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GLOBE OIL & REFINING CO.
Farm- Blackwell No. 1

SEC. 5 T. 31 R. 8W
SE SE NW

Total Depth. 4540'

Comm. 3-1-55

Comp. 3-18-55


Shot or Treated.

Contractor. Ben F. Brack Oil Co., Inc.

Issued. 5-7-55

County Harper

KANSAS



Elevation. 1682' DF

Production. 29.82 BOPD & 10 BW

CASING:

8 5/8" 200' cem w/200 sx
5 1/2" 4538' cem w/100 sx

Figures indicate Bottom of Formations

soil & sand	70
sand & shale	140
red bed & shells	204
red bed & shale	865
lime & shale	1138
shale & shells	1250
salt & shale	1400
shale & lime streaks	1480
lime & shale	1710
lime	1840
sandy lime	1940
lime & shale	2100
lime	2115
lime & shale	3150
lime	3245
lime & shale	3340
lime	3375
lime & shale	3514
lime	3535
shale & sand	3680
shale	3695
lime	3848
lime, broken	3920
lime	4170
lime & shale	4245
lime	4303
lime & shale	4367
lime	4428
chat	4510
chat & lime	4540
Total Depth	

Tops:
Heebner

3422

Base Oread	3496
Douglas Sand	3496
Lansing-Kansas City	3637
Base Kansas	4164
Mississippi Chat	4404
Mississippi Lime	4524

Perforated 50/4414-4424

Acidized 250 gallons mud acid and 250 gallons wash acid

Sandfraced w/3000 gallons Petrojel and 3000# sand.