

5 - 31 - 8 W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GLOBE OIL & REFINING CO.
Farm- Blackwell No. 2

SEC. 5 T. 31 R. 8W
NW NW NW

Total Depth. 4480'
Comm. 10-19-57 Comp. 11-15-57
Shot or Treated.
Contractor, Mull Drlg. Co.
Issued. 4-26-58

County Harper
KANSAS



CASING:
8 5/8" 220.41' cem w/225 sx.
5 1/2" 4478' cem w/150 sx.

Elevation. 1679' RB

Production. State Test
21.71 bbls. oil, 505,953
cu. ft. gas

Figures Indicate Bottom of Formations.

clay	10
sandy clay	80
red bed	725
shale & shells	1375
lime & shale	1820
lime	1950
lime & shale	2320
shale & lime	2915
sandy lime & shale	3120
shale & sandy lime	3360
shale & sandy lime	3692
lime & shale	3803
lime	4017
lime & shale	4068
lime	4344
lime & shale	4373
Mississippi	4480
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Heebner	3412	3410
Toronto	3440	3440
1st Douglas Sand	3470	3470
2nd Douglas Sand	3580	3575
Lansing-Kansas City	3638	3636
Mississippi Chat	4373	4370
Mississippi Lime	4438	4436

11-7-57 Welex Dyna Jet perforated with
56 holes from 4410-4424'.
11-8-57 Dowell acidized 250 gallon mud
acid.
11-9-57 Dowell fraced w/15,000 gallons
Petrofrac and 15,000# sand.