

5-31-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GLOBE OIL & REFINING CO.
Farm- Blackwell No. 3

SEC. 5 T. 31 R. 3W
C NW NE

Total Depth. 4550'

Comm. 9-24-58


Comp. 10-9-58

Shot or Treated.

Contractor. Powell Drilg. Co.

Issued. 12-20-58

County Harper
KANSAS



CASING:

8 5/8" 208' cem w/225 sx.

5 1/2" 4565.61' cem w/150 sx.

Elevation. 1680' RB

Production. 46.76 Oil, 70% Wtr.

Figures indicate Bottom of Formations.

red bed & shells	225
red shale	347
red bed & shale	940
shale & shells	1350
broken anhydrite	1540
lime & shale	1790
lime	2205
lime & shells	2325
shale & shells	2495
lime & shale	3660
lime	3890
shale & lime	3950
lime	4060
lime & shale	4096
sand & shale	4125
lime & shale	4410
Mississippi Chat	4440
chat	4533
line	4550 RTD
Total Depth	

TOPS: GEOLOGICAL R.D. Meas.

Heebner	3424
Lansing	3624
Cherokee	4304
Mississippi Chat	4406
Mississippi Dolomite	4533
RTD	4550
Schlumberger	4550

10-12-58 Lane-Wells perforated 80 holes
from 4408-4428 (Sch. Meas.)

10-13-58 Acidized 500 gallons mud acid
(by Dowell)

10-15-58 Dowell fraced w/12,000 gallons
acid petrofrac and 10,000# 20/40
sand