

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Lario Oil & Gas Company

API NO. 15-077-20751

ADDRESS 301 South Market Street

COUNTY Harper

Wichita, KS 67202

FIELD South Spivey-Grabs

**CONTACT PERSON Robert Miller

PROD. FORMATION Miss. Chat

PHONE (316)265-5611

LEASE Blackwell

PURCHASER Getty Crude Gathering, Inc.

WELL NO. 5

ADDRESS P.O. Box 3000

WELL LOCATION SW SW NE

Tulsa, OK 74102

330 Ft. from West Line and

DRILLING Sweetman Drilling, Inc.

330 Ft. from South Line of

CONTRACTOR


ADDRESS P.O. Box 645

the SEC. 5 TWP. 31S RGE 8W

Great Bend, KS 67530

WELL PLAT

PLUGGING
CONTRACTOR
ADDRESS



KCC
KGS
(Office Use)

TOTAL DEPTH 4550' PBTD 4512' (inside csg)

JD DATE 12-4-81 DATE COMPLETED 12-30-81

ELEV: GR 1674' DF KB

FILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 308.96' (thrds off) DV Tool Used? No

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS, I,

Robert Miller OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Prod. Supt. (X) (OF) Lario Oil & Gas Company

OPERATOR OF THE Blackwell LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 5 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 22nd DAY OF January, 1982, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

OTHER AFFIANT SAITH NOT.

Two

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Sand & Red Bed

Red Bed & Shale

Lime & Shale

Mississippi

Total Depth

0

326

1524

4434

4550

port of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string

Size hole drilled

Size casing set (in O.D.)

Weight lbs/ft.

Setting depth

Type cement

Sacks

Type and percent additives

Surface

12 1/4"

8-5/8"

24#

308.96'

Common

275

2% ge1, 3% CC

Production

7-7/8"

5 1/2"

1 1/2, 1 1/4, 1 1/2

4547'

50-50 Poz

160

10% salt, 3/4 of 1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.

Bottom, ft.

Sacks cement

Shots per ft.

Size & type

Depth interval

2

Jumbo Jets

4404-4415'

TUBING RECORD

Size

Setting depth

Packer set at

2-3/8"

4508.5'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

500 gals 15% MCA acid + 2000 gals 7 1/2% MCA acid & 30 balls

4404-4415'

5- 31- 8w

State Geological Survey

WICHITA BRANCH

JAN 22 1982

WELL LOG
Blackwell #5
SW SW NE 5-31S-8W
Harper County, Kansas

Name of Operator: Lario Oil & Gas Company
301 S. Market
Wichita, Kansas 67202

Date Completed: 12-13-81

<u>FROM</u>	<u>TO</u>	
0	326	Sand and Red Bed
326	1524	Red Bed and Shale
1524	4434	Lime and Shale
4434	4550	Miss.
4550		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss

Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.


Gary L. Hawk