

7-31-8W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


Company - DRILLERS GAS COMPANY  
Farm - Wingate No. 2

SEC. 7-31-8W 31 8W  
NE SW SW

Total Depth. 4429...  
Comm. 1-23-50 Comp. 2-9-50  
Shot or Treated.  
Contractor. Beardmore Drilling Co.  
Issued. 5-13-50



County. Harper  
KANSAS



1629(x)

Elevation. 1632 *ft*

CASING:  
8 5/8" 292' cem w/125 sx  
5 1/2" 4373' cem w/100 sx

Production. Guage 1,131,000  
cu. ft. gas / 6 BOPD &  
19 bbls. water pr day.

Figures Indicate Bottom of Formations.

surface soil	20	
sand	110	
red bed, shale	275	
cement	292	
shale	690	
shale, shells	1065	
salt, shells	1295	
lime, shale	1450	
lime	1620	
lime, shale	1925	
lime	2025	
lime, shale	2815	
K. C. line	2885	
lime, shale	3145	
shale	3215	
lime, shale	3650	
lime	4360	
Mississippi	4373	RTD
lime	4429	
Total depth		
Tops:		

Lansing 3620  
Mississippi 4369

90 qts nitro 4385-4425