

8-31-8W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- FRANK PURCELL ET AL  
Farm- Dickson No. 2

SEC. 8 T. 31 R. 8W  
SE SE NW

Total Depth. 4405  
Comm. 2-26-54 Comp. 3-14-54  
Shot or Treated.  
Contractor. Pickrell Drlg. Co.  
Issued. 5-22-54

County Harper  
KANSAS



CASING:

8 5/8" 160' cem. w/150 sx  
5 1/2" 4386' cem.w/200 sx

Elevation. 1638

Production. 69 BO / 6% water

Figures Indicate Bottom of Formations.

|                         |          |
|-------------------------|----------|
| sand                    | 85       |
| redrock                 | 180      |
| redbed & shale & shells | 990      |
| shale & shells          | 1335     |
| Anhydrite               | 1375     |
| shale & shells          | 1420     |
| lime                    | 2025     |
| lime & shale            | 2235     |
| shale                   | 2705     |
| shale & lime            | 2860     |
| lime                    | 2990     |
| shale & lime            | 3105     |
| lime                    | 3390     |
| lime & shale            | 3475     |
| lime                    | 4275     |
| lime & shale            | 4325     |
| chert                   | 4396 RTD |
| chert                   | 4405     |
| Total depth             |          |

Circ. for samples at 4355'  
" " " " 4376'

SIM 2025 - O.K.  
Slope Test @ 2205 0° off

SIM 4325 O.K.  
Slope test @ 4325 -0° off.

All meas. from top of rotary bushing

Tops: Scout  
Lansing 3637  
Mississippi 4386