


15-31-8W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ROBINOWITZ OIL CO. & PET. OPERATING CO. SEC. 15 T. 31 R. 8W
Farm- Stephens No. 1 NW SE NW

Total Depth. 4485'
Comm. 2-8-64 Comp. 2-21-64
Shot or Treated.
Contractor. Sholom Drilling Co., Inc.
Issued. 6-13-64

County Harper
KANSAS



Elevation. 1615' KB

Production. 50 BOPD / 130 BWPD

Figures indicate Bottom of Formations.

clay & sand	90
shale	166
shale & redbed	1278
Anhydrite	1335
shale	1500
lime & shale	3590
lime	3893
lime & shale	3935
lime	4389
chert	4404
chert ?	4485 RTD
Total Depth	

TOPS: LOG	
Heebner	3380
Toronto	3412
Douglas	3515
Lansing	3640
Base Lansing	3770
Kansas City	3884
Base Kansas City	4137
Mississippi	4389

DST 4391'-4404' 20' mud, 120' oil cut
mud, 210' very heavy oil cut mud, 120'
muddy oil, 30' wtr., BHP 1480, FBHP
1360, Flow 60-80.

DST 4406-4424' Rec. 30' oil cut mud,
370' heavy oil cut mud, 60' wtr. BHP
1300#, Flow 0-120#

Schlumberger-Gamma Ray, Laterlog, Sonic run at T.D.