

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


18-31-8W

Company: BEARDMORE DRILLING CO. ET AL
Form: Darnes No. 1

SEC. 18 T. 31 R. 8W
NE NW NW

Total Depth. 4459 PB 4428'
Comm. 11-30-52 Comp. 1-13-53
Shot or Tested.
Contractor: Beardmore Drlg. Co.
Issued. 7-11-53

County Harper
KANSAS



CASING:
8 5/8" 195' cem. w/100 sx
5 1/2" 4439' cem. w/75 sx

Elevation. 1611 DF

Production. Pmp. 30 BO & 35 BW

Figure indicates Bottom of Formations.

cellar	5
sand	55
red rock	70
shale, shells	195
shale red	710
shale, shells	1375
lime, shale	2010
shale, lime	2725
lime, shale	3395
lime broken	3465
lime	3524
lime sandy	3630
lime	4376
lime, chert	4382
lime cherty	4399
chat	4415
chert	4445
chert	4459

Total Depth PB 4428'

Tops:
Lansing 3606
Mississippi 4357

DST: #1 4375-4382' open 1 hr.
shut in 15 mins. rec. 85' of
very slightly gas & oil cut
mud. BHP 900#.

DST: #2 4382-4399' open 1 hr.
shut in 15 mins. rec. 210'
fluid. Top very slight oil
& gas cut mud. Oil cut mud
heavier last 30'. BHP 645#.

Cable Tools 4445-4458 chat, slight
show oil 1/2 bbls. water per hr.
Plugged back to 4428' perf. 4410'-
4420' with 72 shots, 2 bbls.
per hr. 50% water. Perf. 4391'-
4397' with 48 shots. four bbls.
per hr. 40% water.