

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA BRANCH

PL

API No. 15 — 077 — 20,712
County Number

Operator

McLOY PETROLEUM CORPORATION

Address

One Main Place / Suite 410

Well No.

1

Lease Name

HONN "A"

Footage Location

2310

feet from (S) line

1650

feet from (W) line

Principal Contractor

Sweetman Drilling, Inc.

Geologist

Robert L. Smith

Spud Date

8-4-81

Date Completed

9-19-81

Total Depth

4388'

P.B.T.D.

4388'

Directional Deviation

None


Oil and/or Gas Purchaser

Koch - Peoples

S. 20 T. 31 R. SE W

Loc. NW NE SW

County Harper

640 Acres
N

Locate well correctly

Elev.: Gr. 1591

DF 1598 KB 1601

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24*	237'	Common	225	2% gel 3% Calcium Chloride
Production	7 7/8"	4 1/2"	10.5#	4376'	Common	125	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
				Open hole	4376-4388'

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	4373'	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid 750 gallons 7 1/2% MCA	4376-4388'
Frac 5500 gallons Versagel x 3000# 20/40 sand	4376-4388'

INITIAL PRODUCTION

Date of first production 9-14-81		Producing method (flowing, pumping, gas lift, etc.) Pump			
RATE OF PRODUCTION PER 24 HOURS	Oil 44 bbls.	Gas 112 MCF	Water 73 bbls.	Gas-oil ratio 2545 CFPB	
Disposition of gas (vented, used on lease or sold) Sold			Producing interval(s) 4376-4388' Mississippi		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator <i>McCoy Petroleum Corporation</i>		DESIGNATE TYPE OF COMP.: OIL, GAS DRY HOLE, SWDW, ETC.:
Well No. <i>1</i>	Lease Name <i>Honn "A"</i>	<i>Oil + Gas</i>
S <i>20</i> T <i>31</i> R <i>8</i> <i>E</i> W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<i>See attached Report.</i>				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	Signature
	Title
	Date