

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCHAPI No. 15 — 077 — 20522
County Number

Operator

McCoy Petroleum Corporation

Address

One Main Place / Suite 410 Wichita KS 67202

Well No.

1

Lease Name

Williams "E"

Footage Location

1650

2370

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Sweetman Drilling Inc.

Geologist

Deane Jirrels

Spud Date

5-16-79

Total Depth

4442'

P.B.T.D.

Date Completed

0-12-79


Oil Purchaser

Koch Cities (Gas)

S. 22 T. 31 S. R. 8 E W

Loc. SE NE SW

County Harper

640 Acres
N

Locate well correctly

Elev.: Gr. 1621

DF 1628 KB 1631

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28*	256'	Common	250	7% Gal 3% Cal Chlor
Production	7 7/8	4 1/2	10.5*	4436'	Common	150	

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
----------	-------------	--------------	---------------	-------------	----------------

TUBING RECORD

Size	Setting depth	Packer set at			
2 3/8 EOE	4438'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
6-7-79 FRAC 4500 gallons VAF-2 and 3000# of 20/40 sand	4436' - 4442'

INITIAL PRODUCTION

Date of first production 0-13-79		Producing method (flowing, pumping, gas lift, etc.) Pump			
RATE OF PRODUCTION PER 24 HOURS	Oil 5 bbls.	Gas 20 MCF	Water	Gas-oil ratio 4000 bbls.	CFPB
Disposition of gas (vented, used on lease or sold) Sold			Producing interval (s) 4436'-4442'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 3830 So. Meridian Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator McCoy Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil + Gas		
Well No. 1	Lease Name Williams "E"			
S 22 T 31 R 8W ^E _W				
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
See attached report				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	Signature Title Date			

P

22-31S-8W

WELL LOG
Williams E #1
SE NE SW 22-31S-8W
Harper County, Kansas

State Geological Survey
WICHITA, BRANCH

Name of Operator: McCoy Petroleum Corporation
One Main Place Suite 410
Wichita, Kansas 67202

Date Completed: May 22, 1979

<u>FROM</u>	<u>TO</u>	
0	105	Sand
105	256	Red Bed
256	540	Red Bed and Sand
540	1105	Shale
1105	4329	Lime Shale
4329	4442	Lime
4442		Total Depth

STATE OF KANSAS

COUNTY OF BARTON

Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1979

CONSERVATION DIVISION
Wichita, Kansas


Gary L. Hawk

Subscribed and sworn before me this 29th day of May, 1979.