

KANSAS DRILLERS LOG 15-077-20298

API No. 15 - 077 - 20298  
 County Number


KANSAS GEOLOGICAL SURVEY  
 Wichita, Kansas

S. 22 T. 31 R. 8 <sup>EX</sup><sub>W</sub>

Loc. C. SE NW

County Harper

640 Acres  
N



Locate well correctly

Elev.: Gr. 1576

DF 1578 KB 1581

Operator Petroleum, Inc.

Address 800 R.H. Garvey Bldg., 300 W. Douglas, Wichita, Ks.

Well No. 1 Lease Name WILLIAMS 'K'

Footage Location  
 feet from (N) (S) line \_\_\_\_\_ feet from (E) (W) line \_\_\_\_\_

Principal Contractor \_\_\_\_\_ Geologist \_\_\_\_\_

Spud Date 2-10-75 Total Depth 4411' P.B.T.D. \_\_\_\_\_

Date Completed 2-20-75 Oil Purchaser \_\_\_\_\_

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	208'	Common	225 sx.	2% gel, 3% c.c.

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production \_\_\_\_\_ Producing method (flowing, pumping, gas lift, etc.) \_\_\_\_\_

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval(s) \_\_\_\_\_

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Petroleum, Inc.	DESIGNATE TYPE OF COMP.: DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Williams 'K'
Dry	

S 22 T 31 S R 8 ~~XXXXXX~~ W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4383-91 30-30-60-90 Wk blow inc. to strong. Rec. 25' mud (no show) IFP 18#-18# FFP 18#-27# BHP 354#-1046#			DRESSER-ATLAS	LATEROLOG
			Hb. 3362	(-1781)
			KC 3877	(-2296)
			Stk. 4024	(-2443)
			Hertha 4060	(-2479)
			Ft. St. 4275	(-2694)
			Miss. 4384	(-2803)
DST #2 4383-4401 30-30-60-90 Strg. blow. Rec. 120' mud (spk oil) 20' water IFP 50#-80# FFP 80#-100# BHP 769#-1241# 120°				
DST #3 4401-11 30-30-60-90 Strg Blow Rec. 20' sl. OCM, 60' mdy wtr. (sso) 240' clear SW IFP 60#-90# FFP 90#-180# BHP 1412#-1503 T. 124°			LTD 4410	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Jay McNeil</i> Signature
	District Geologist Title
	March 4, 1975 Date