

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


30-31-8W

Company- MAGNOLIA PETROLEUM CO.
Farm-W. L. Carr No. 3

SEC. 30 T. 31 R. 8W
SE NE SW

Total Depth. 4385
Comm. 4-26-56 Comp. 6-6-56
Shot or Treated.
Contractor. Harry Bass Drilling Co.
Issued. 8-18-56

County Harper
KANSAS



Elevation. 1565 DF

Production. 27 BO, 236 BWPD

CASING:

9 5/8 @ 238' w/ 250 sx cmt.
5 1/2 @ 4372' w/ 200 sx cmt.

Figures indicate Bottom of Formations.

red bed & sand	137
shale & red bed	360
shale; red bed & anhydrite	1243
shale, anhydrite & lime	1655
lime; shale & gypsum	1800
lime; shale & anhydrite	2088
lime; shale & gypsum	2463
lime; gyp & anhydrite	2663
lime, gypsum & shale	3595
lime & shale	3992
lime & chert	4009
lime, chert & shale	4049
lime	4082
lime & shale streaks	4129
lime & shale	4365
Mississippi chat	4385
Total Depth	

TOPS:
Lansing 3632
Mississippi 4362

DST #1: 1647-1825; open 1 hr. good bl.
rec. 50' wtry mud, 938' muddy SW,
FBHP 520#, SIBHP 745#/20 min.

DST #2: 4363-77, open 1 hr. gas 10 min.
481 MCF/60 min; rec. 75' G&OCM, 30'
G&MCO, 220' FO, 20' MW, FP 150-240#,
BHP 1575#/30 min.

DST #3: 4377-85; open 1 hr. fr. bl.
rec. 120' G&OCM, FP 0-0#, BHP 1200#/30
min.