

31-31-8W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- W. L. Carr No. 1

SEC. 31 T. 31 R. 8W
SW NW NW

Total Depth. 4460
Comm. 6-20-54 Comp. 7-27-54
Shot or Treated.
Contractor. Prime Drilling Co.
Issued. 11-6-54

County Harper
KANSAS



CASING:

9 5/8 @ 255' w/ 225 sx cmt.
5 1/2 @ 4459' w/ 200 sx cmt.

Elevation. 1555 DF

Production. P 43 BO, 20 BSWPD

Figures Indicate Bottom of Formations.

sand & clay	50
red bed & shale	255
shale & shells	1315
anhydrite	1330
shale & shells	1500
lime & shale	1665
lime w/ shale breaks	3225
lime & sandy shale	3320
lime & shale	3395
lime w/ shale breaks	3440
lime & shale	3595
lime	3675
lime w/ shale breaks	3968
lime	4005
shale	4295
shale w/ lime	4355
Mississippi lime	4460
Total Depth	

TOPS:
Mississippi 4375

DST #1: 4374-4406, open 1 hr, SI 30 min.
gas to surf 5 min. rec. 1620' gassy
oil, 235' HO&GCM, 125' water-chiefly
filtrate, FP 93-387#, BHP 1345# still
building.

DST #2: 4406-20, open 1 hr. SI 30 min.
strong blow deareas. to fair blow.
rec. 570' gas, 90' GC&SOCM, 240' wtr.
FP 42-139#, BHP 1495#