


8-240

Map No. K-83OPER SATURN OIL & GAS COMPANYCheyenne, WyomingWELL #2 MASON "A"TR Moran BrothersFIELD Panoma Pool (C Gr Gas)I.P. OF: 563,000 CFGPD, SICP 287.4#, SITP 287.4CG 2844-93

RTD 2980, Log, 4 1/2" @2979' w/225 Sx.,  
 Pf 40/2918-28 (CG), 500A, § 10-16 BWPW, sho gas/11 hrs,  
 Sq pfs, 2918-28 w/200 Sx., Pf 8/2891-93, 40/2844-54, 28/  
 2867-74 (CG), § dry, 2500A, Frac 16,750 gal gell wtr,  
 22,000# sd, § 1d w/s11 sho gas, Re-Acid 2500A, 17,500 gal  
 wtr, 8500# sd, § 12 BLW, sho gas/PH, Re-Frac 60,000 gal  
 wtr, 33,000# sd, Gas Ga 240,000 / 6 BLW/PH - § 400,000  
 Cfgpd & 1 1/2 BWPW, Clor 40,000 PPM

Ran 1 1/2" tbg @2862, Ga 416,000 Cfgpd & 15 gal wtr/PH,  
 FCP 225#, SICP 305#/20 hrs, 2 hr BD Ga 664,000 Cfgpd  
 thru tbg, FCP 220#, SITP 320#/20 hrs, SICP 325#/20 hrs,  
 Ga 8 hr BD 519,000 Cfgpd - 4 hr BD, Ga 519,000 Cfgpd,  
 FCP 250#, 1 Pt Cal OF: 563,000 CFGPD, SICP 287.4#, SITP  
 287.4#, CG 2844-93 COMPLETED on 8-23-65

S-T-R 8-31S-37WSPOT App C NWCO STEVENS, Ks.ELEV 3106 KB

GR Log

Kri 2456 / 645

Winf 2526 / 575

CG 2764 / 337

LTD 2971 / 130

Data Inc*Liberal E. Log Topo*

3101 GR

Winf 2526 + 575

C.G. 2782 + 319 @ 563 MCF

TD 2971

MISCELLANEOUS DATA

GEOL \_\_\_\_\_

FTG \_\_\_\_\_

SUPPT \_\_\_\_\_

CSG \_\_\_\_\_

ELEV 3101 GR2-5 3104 DFSPUD DATE 6-7-65

DRLG COMP \_\_\_\_\_

FR by DATA 5-5-65COMP by " 8-26-65

8" @629' w/400 Sx. 4" @2979' w/225 Sx.