

2-31-9W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- TEXACO, INC. No. 1
Farm- Joe Brummer

SEC. 2 T. 31 R. 9W
C NW SE
1980' W & 660' S of NE cor SE¹

Total Depth. 4486'
Comm. 9-12-59 Comp. 9-28-59
Shot or Treated.
Contractor Capitt Drlg. Co.
Issued. 2-27-60

County Harper KANSAS



Elevation. 1695' RB

CASING:

7 5/8" 372' cem.w/350 sx.
4 1/2" 4485" cem.w/75 sx.

Production. 232 BOPD &
306 MCF Gas
from perfs. 4458-70' and
slot at 4464'

Figures Indicate Bottom of Formations.

sandy clay	25
sand	100
sandy shale & shells	170
shale & shells	370
red bed	595
shale & shells	1130
shale w/lime strks.	1500
lime & shale	1562
lime	1590
lime & shale strks..	1606
lime	2059
lime & shale	2231
shale & lime	2345
lime & shale	2748
shale & lime	2875
shale & shells	3000
shale & lime	3163
lime	3280
lime & shale strks.	3376
lime	3515
lime w/shale strks..	3629
sand & shale	3700
lime	4417
chat	4485 RTD
chat	4486
Total Depth	

TOPS: Scout
Lansing 3698
Mississippi 4424