

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


6-31-9W

Company: MAGNOLIA PETROLEUM CO.  
Farm: M. Jacobs "B" No. 1

SEC. 6 T. 31 R. 9W  
SW NE NE

Total Depth. 4485  
Comm. 11-5-55 Comp. 12-12-55  
Shot or Treated.  
Contractor. Bass Drilling Co.  
Issued. 2-11-56

County Harper  
KANSAS



Elevation. 1644 DF

Production. Dry

CASING:

9 5/8 @ 251' w/ 275 sx cmt.  
5 1/2 @ 4484' w/ 200 sx cmt.

Figures Indicate Bottom of Formations

red bed & sand rock	138
red bed	300
red bed & shale	1326
shale & lime streaks	1641
lime & shale	1875
lime, shale & anhydrite	1925
lime & shale	2643
lime, shale & gypsum	3168
lime & shale	3215
lime, gypsum & shale	3256
lime & shale	3304
lime, gypsum & shale	3385
lime & shale	3816
lime	3965
lime & shale	3993
lime	4005
lime & shale	4019
lime, gypsum & shale	4040
lime & shale	4350
lime, sand & shale	4363
Mississippi chat	4399
chert, lime & shale	4428
lime	4443
lime, chert, shale, dolomite	4485
Total Depth	

TOPS:

Lansing	3682
Burgess	4352
Mississippian	4366

DST #1: 4364-87, open 1 hr, good bl.  
gas to surf. 42 min. rec. 70' SGCM,  
FBHP 40#, BHP 740#/30 min.