

10-31-9W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. RUPP-FERGUSON OIL CO.
Farm. Miller "B" No. 1

SEC. 10 T. 31 R. 9W
C SE SE

Total Depth. 4470'
Comm. 2-11-58 Comp. 2-23-58
Shot or Treated.
Contractor. Rupp-Ferguson Oil
Issued. 6-7-58

County Harper
KANSAS



Elevation. 1653' KB

Production. 4,000,000 CFG
and 60 BOPD

Figures indicate Bottom of Formations.

surface soil & sand	138
red bed & shale	430
salt	730
brown lime & shale	910
shale & shells	1244
lime	1250
shale & shells	1466
lime & shale streaks	1657
lime	1790
sandy lime	1800
lime & shale	1950
shale & lime streaks	2080
shale	2265
lime & shale	2605
shale	2815
lime & shale	2957
lime, shale & sand strks	3171
lime & shale	3500
lime, shale & sand streaks	3648
lime	3904
lime, shale streaks	3963
lime	4068
lime & shale	4119
lime	4257
lime & shale	4368
Mississippi	4470
Total Depth	

TOPS:	SCHLUMBERGER
Douglas	3516
Lansing-Kansas City	3658
Base Kansas City	4177
Mississippi	4374

DST 4420-4445, open 1 hr., gas to surface in 7 min. In 10 min. gauged 324,000. At end of 22 min. had dec. to 44,000. Started flowing oil in 55 min.

DST 4378-4420, open 1 hr, gas to surface in 2 min., at end of hr. gauged 3,310,000 rec. 100' OGCM. IFP 760#, FFP 760#, IBHP 1680#, FBHP 1600#.