

13-31-9W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- HARRY BASS DRILLING COMPANY
Farm- L. W. Ryan No. 8

SEC. 13 T. 31 R. 9W
NE NE SW

Total Depth. 4435
Comm. 12-4-54 Comp. 12-18-54
Shot or Treated.
Contractor. Purcell-Mull Drlg Co., Inc.
Issued. 6-11-55

County Harper

KANSAS



Elevation. 1607 D.F.

8 5/8" CASING: 192' cem w/150 sx
5 1/2" 4433' cem w/250 sx

Production. State Pot. 233 BO

All meas. from top of Rotary Bushing. Figures indicate Bottom of Formations

sand	70
red rock	192
red rock, red bed	480
red bed, shale	700
shale, hells	1360
salt, shale, lime	1490
lime, shale	1818
lime	1960
lime, shale	3145
lime, sand	3288
shale, lime	3491
sand, shale	3550
lime, shale	3645
lime	3836
lime, shale	3905
lime	4333
lime, shale	4354
lime (Miss.)	4435
Total Depth	RTD

Tops: Scout.
Mississippian 4354

Drill Stem Test #1. 4390-4415, gas to surface in 6 1/2 mins., guaged 600,000 in 8 mins., guaged 196,00 in 15 mins. too weak to gauge in 30 mins., started to flow in 68 mins. flowed into pits approx. 1 hr. & 40 mins & into tanks for 2 hrs through 3/8" choke; flowed 30 bbls in 2 hrs, flushed oil out of tool, had 10' of wtr below circulating valve. I.F.P. 254# F.F.P. 1042#. BHSIP 1602# in 30 mins.