

15-31-9W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. RUPP-FERGUSON
Farm. Miller "C" No. 1

SEC. 15 T. 31 R. 9W
NE NE NW

Total Depth. 4440'
Comm. 5-23-58 Comp. 6-4-58
Shot or Treated.
Contractor. Rupp-Ferguson Oil Co.
Issued. 8-16-58

County Harper
KANSAS



CASING:
8 5/8" 258' cem w/185 sx.
5 1/2" 4440' cem w/100 sx.

Elevation. 1655' RB

Production. 10,367,000 CFG

Figures Indicate Bottom of Formations.

surface soil & sand	90
red clay, sand, rock	155
sandy rock	165
red bed & rock	259
shale	510
red bed, clay, sand	
streaks	725
shale	1355
lime & shale	1760
shale, lime, sand stks	1930
lime & shale	2342
shale	2642
lime & shale	3572
sand & shale	3673
lime	3689
lime & shale strks	3778
lime	4171
shale & lime	4200
lime	4257
lime & shale	4312
shale	4346
lime & shale	4376
Mississippi	4440
Total Depth	

TOPS: SCHLUMBERGER
Douglas 3510
Lansing-Kansas City 3673
Base Kansas City 4192
Mississippian 4373

DST 4378-4410, op 20 min, gas to surface
in 2 min, gauged 2880 MCF at end of test.
Rec. 120' HGCM. FBHP 1600#,