


16-31-9W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
Farm- Donald Muir Gas No. 1
Unit

SEC. 16 T. 31 R. 9W
SW NW SE
2210' W & 1650' N of
SEc SE/4

County Harper KANSAS



1700' DE

Elevation. _____

Production. 1,558,000 MCFGPD

Total Depth 4518' PBD 4509'
Comm. 12-1-56 Comp. 1-1-57
Shot or Treated.
Contractor. Stickle Drilling Company
Issued. 2-9-57

CASING:

10 3/4" @338' w/350 sx. cem.
7" @4517' w/200 sx cem.

Figures indicate Bottom of Formations

sand	50
shale & sand	125
shale & shells	340
shale	850
Anhydrite	890
shale & shells	1250
shale & lime	1600
lime	1750
lime & shale	1860
lime	2010
shale & lime	2780
shale & shells	2795
lime & shale	3150
sandy lime & shale	3180
lime & shale	3255
lime	3350
lime & shale	3495
lime & sand	3585
lime & shale	3665
sand & shale	3755
lime	4457
Chat	4475
Mississippi Chat	4518
Total Depth	
PBD	4509
TOPS	
Douglas	3577
Douglas Sand	3627
Lansing	3743
Base/Kansas City	4257
Marmaton	4291
Cherokee	4395
Mississippi	4457