

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-31-9W

Company- ORVILLE H. PARKER
Farm- Darnes Estate No. 1

SEC. 24 NW NW SW 31 R. 9W

Total Depth. 4497
Comm. 3-22-55 Comp. 4-6-55
Shot or Treated.
Contractor. Prime Drilling Co.
Issued. 8-6-55

County Harper
KANSAS



CASING:

8 5/8 @ 230' w/ 175 sx cmt.
5 1/2 @ 4497' w/ 100 sx cmt.

Elevation. 1613

Production. 212 BO

Figures indicate Bottom of Formations.

clay & sand	70
red bed & shale	655
shale, sand & lime streaks	1195
shale & shells	1350
anhydrite	1380
shale & lime	1505
shale & sandy lime	2260
shale & lime	2405
shale & sandy lime	2725
lime & shale	2840
broken lime & shale	3075
lime & shale	3130
sandy lime & shale	3375
lime & shale	3455
sand & lime	3650
lime	3715
shale & lime	4010
lime	4055
lime & shale	4315
Mississippi chert	4400
chert & lime	4405
chert	4420
chert & lime	4430
lime, chert & cherty lime	4497
Total Depth	

DST #1: 4384-4400, open 1 hr. gas to surf. 2 1/2 min. gauged 277 MCFG, rec. 20' HGCM. 260' muddy oil, 190' gassy oil, 10' muddy water, IFP 72#, FFP 205#, BHP 1610#/20 min.

DST #2: 4400-10, open 1 hr. rec. 1200' gas, 95' GC&SOCM, 60' muddy water, IFP 15#, FFP 60#, BHP 695#/20 min.

DST #3: 4410-20, open 1 hr. gas to surf. 35 min. rec. 30' O&GCM, 90' VH)&GCM, 60' emuls. oil, 30' SW, IFP 30#, FFP 100#, BHP 1315#/30 min.

TOPS:	SAMPLE	E. L.
Heebner	3444	3443
Upper Douglas	3552	3554
Lower Douglas	3604	3606
Lansing	3638	3638
Base KC	4180	4180
Mississippi chert	4382	4382

Electric Log TD 4500