

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

24-31-9W

Company- ORVILLE H. PARKER et al
Farm- Darnes Estate No. 2

SEC. 24 T. 31 R. 9W
SE NW SW

Total Depth. 4500

Comm. 5-25-55

Comp. 6-9-55

Shot or Treated.

Contractor. L. C. Smitherman Drilling Co.

Issued. 12-31-55

County Harper
KANSAS



CASING:

8 5/8 292' w/ 200 sx cmt.

5 1/2 4500' w/ 125 sx cmt.

Elevation. 1604. BB

Production. 295 BOPD

Figures indicate Bottom of Formations

sand	100
shale & sand	200
shale & shells	270
sand	280
lime	292
lime & shale	314
red rock	380
shale & shells	470
shale	995
shale & shells	1455
shale	1540
lime	1615
lime w/ shale streaks	1785
lime	1940
lime & shale	1955
lime	2170
shale & lime	2950
lime	3010
lime w/ shale streaks	3140
lime	3205
shale & shells	3225
shale & lime	3365
lime	3396
lime w/ shale streaks	3499
lime	3565
shale & lime	3634
lime	4134
lime & shale	4176
lime w/ shale streaks	4226
lime & shale	4377
Mississippi lime	4500
Total Depth	

SCOUT TOPS:

Heebner	3438
Douglas sand	3504
Lower Douglas sand	3602
Lansing	3628
Base K. C.	4170
Mississippi	4367
Mississippi chert	4377