

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

24-31-9W


Company- O. H. PARKER
Farm- Darnes

No. 2

SEC. 24 T. 31 R9W
NE NW NE

Total Depth. 4450' PB 4426' SLM
Comm. 12-9-55 Comp. 12-22-55
Shot or Treated.
Contractor. Gabbert-Jones Drlg. Co.
Issued. 5-11-57

County Harper
KANSAS



Elevation. 1596' KB

Production. 111 BOPD/15% wtr.

CASING:

8 5/8" 305' w/250 sx cem.
5 1/2" 4445' w/150 sx cem.

Figures indicate Bottom of Formations.

sand-clay	55
red bed	170
shale-shells	1395
Anhydrite	1575
shale-lime	1915
lime	2040
lime-shale	2420
shale-shells	2620
shale-lime	2945
shale	2995
lime	3090
lime-shale	3300
shale	3310
lime	3330
lime-shale	3425
lime	3535
shale-sand	3590
lime	3815
shale-lime	3890
lime	3915
lime-shale	3970
lime	4445 RTD
lime	4450
Total Depth PB 4426' SLM	

TOPS:
Heebner 3405
Lansing 3606
Kansas City 3882
B/Kansas City 4138
Mississippi 4349

TOPS: Radiation Guard Log.
Heebner 3408
Lansing 3603
Kansas City 3892
B/Kansas City 4138
Mississippi 4352

DST #1 - 4348-70 Gas in 2 1/2",
7 mscf/40", 4 mscf/50", open
1 hr., rec. 50' oil & GCM,
130' gassy emulsified oil,
BHP 1530#/70".

DST #2 - 4370-90. Gas in 3 1/2".
T.S.T.M. open 2 hrs., Rec.
420' gassy emulsified oil,
90' wtr. IHP 1240#/20" F.B.H.P.
1180#/20".

Perf.: 12-29-55 4385-4390-
Swabbed 35 BO & 17 BW.

Perf.: 1-2-56 4380-4385;
4375-4380 Gas to surface in
2 1/2", filled up 3000' oil in
30".