

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-31-9W

Company- ORVILLE H. PARKER
Farm- Darnes No. 3

SEC. 24 T. 31 R.9W
NW SW SW

Total Depth. 4462 PBTD 4423
Comm. 11-21-55 Comp. 12-7-55
Shot or Treated.
Contractor. Gabbert-Jones Drilling Co.
Issued. 2-4-56

County Harper
KANSAS



CASING:

8 5/8 @ 295' w/ 225 sx cmt.
5 1/2 @ 4459' w/ 150 sx cmt.

Elevation... 1580 DE

Production. 55 BOPD

Figures indicate Bottom of Formations.

sand	40
red bed, sand & shale	295
red bed	310
red bed & shale	815
shale	1050
salt	1100
shale & shells	1345
anhydrite & shale	1510
lime	1615
lime & shale	1830
lime	2037
lime & shale	2490
shale & shells	2600
shale & lime	2820
lime	3155
lime & shale	3545
lime	3555
sand	3613
lime	3920
shale & lime	3934
lime	4382
chert & lime	4462
Total Depth	

Schlumberger TD 4458

Plugged back to (SLM) 4423

TOPS:	E. LOG	SAMPLE
Heebner	3415	3419
Lansing	3614	3613
Base K. C.	4158	4167
Mississippi	4361	4365

Ran Schlumberger & Lane-Wells Logs.

DST #1: 4366-82, open 1 hr, gas in 15 min, rec. 135' HGCM & SOCM, 50' sl. muddy gassy oil, BHP 1540#/20 min.

Perf. 6 SPF/4374.5-4380.5

FU 700' oil, 100' wtr/12 hrs.