

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-31-9W

Company- STANOLIND OIL & GAS COMPANY
Farm- May Golden Ison No. 2

SEC. 24 T. 31 R. 9W
NW SW NW
990' N of SL & 330' E of WL
NW/4

County Harper
KANSAS

Total Depth. 4500; PB 4476
Comm. 12-19-54 Comp. 1-6-55
Shot or Treated.
Contractor.
Issued. 4-2-55



CASING:

8 5/8" 198' ccm. w/250 sx Halliburton
5 1/2" 4499' ccm. w/200 sx "

Elevation. 1606 RDB

Production. 258 BO & 139 BW .

Figures indicate Bottom of Formations.

sand & clay	110	Drilled from 4460-4500
redbed	200	Top of cement behind csg. @ 3400
redbed & shale	620	Perforated - Wellex 4 shots per foot 4412-24
shale & shells	1290	Ran 2 7/8 tubing landed @ 4367
Anhydrite	1600	Acidized w / 500 gal. MCA
shale & shells	1608	Max. Pressure- 1800#
shale	1770	Press, Break to - 800#
lime & shale	2100	Test: 12 hr. swab 3 1/2 BOPH
shale	2163	Sand oil Frac. Halliburton through open
shale & lime	2575	end tubing - 5500 gal. Hvy crude
shale	2661	3100# sand
lime & shale	3096	Break down Press. - 2000-2500
lime	3159	Max. treating Press. - 4700
lime & shale	3500	Min. treating Press. - 2500
sand, lime & shale	3570	Treating time - 42 min.
sand	3616	Test: After recovering load oil
lime	3627	Flow 12 BOPH, 5 BWPH
lime	3630	Tubing Press. Flowing - 175
sand & lime	3640	Casing Press. Flowing - 50
lime	3873	Test -Flowing 12 BOPH, 7 BWPH
lime & shale	3937	Tubing Press. Flowing -200
lime	4133	Casing Press. Flowing -300
lime & shale	4275	State Potential Pumping, 258 BO w/35% wtr.
lime	4375	Corrected Gravity 28
lime, chert, oil & gas	4400	Mississippi 4375-4500
lime, chert Oil, gas & wtr	4430	
lime, chert, gas Water	4460	
lime & chert	4500	

Total depth; PB 4476
Ran Sch. Elec log TD
TD By Electric Logs 4500
By Rotary Drill 4500

Remarks:

Miss. Formation
Perforated Interval 4412-4424

Tops:

Lansing 3627
Mississippi 4375

DST #1 TD 4400

Packer set @ 4375, Tool open 1 hour, gas
to surface 4 minutes 434 MCF per day
Rec. 75' oil & gas cut mud - 120' Free oil
60' mud and gas cut oil

BHPSI 1500

DST #2 TD 4430

Packer set @ 4400 - Tool open 1 hour,
gas to surface 30 minutes - Rec. 330'
free oil - 60' mud and gas cut oil
105' oil and gas cut mud - 60' salt water.

BHPSI - 1445

DST #3 TD 4460 - Packer set @ 4430;

Tool open 1 hour, no gas to surface.
Rec. 150' oil and gas cut mud, no wtr.

BHPSI - 780