


API#15-077-20, 166

DEC 29 1972

ROTARY DRILLERS' LOG



26-31-9W

Broce 1

OPERATOR: SeRoBee Drilling Co.
and Shaffer Oil Co.
256 North Topeka
Wichita, Kansas 67202

DRILLING COMMENCED: October 12, 1972

CONTRACTOR: Graves Drilling Co., Inc.
505 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: October 20, 1972

CASING RECORD: 10 Jts. 216' 8-5/8"
cemented with 150 sacks.
104 Jts. 4423' 5-1/2"
cemented with 100 sacks.

LOCATION: Broce No. 1
C W/2 SE SE
Section 26-31S-9W
Harper County, Kansas

1603 KB

35 BopD

L

Smp Tops

LANS. 3655
BKC. 4209
MISS 4419
RTD 4435

0 - 221 Red bed
221 - 340 Red bed & shale
340 - 1365 Shale & shells
1365 - 1430 Shale & lime
1430 - 1670 Lime & shale
1670 - 1990 Shale & lime
1990 - 2182 Lime
2182 - 3245 Shale & lime
3245 - 3301 Lime
3301 - 3362 Shale
3362 - 3488 Lime
3488 - 3565 Shale & lime
3565 - 3610 Sand
3610 - 3635 Lime
3635 - 3805 Lime & shale
3805 - 4195 Lime
4195 - 4300 Lime & shale
4300 - 4435 Lime & chert

4435. Rotary Total Depth

we hereby certify the foregoing statements to be true and correct to the best of our knowledge.

