

26-31-9W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- CHAMPLIN REFINING CO.  
Farm- Rall No. 1


SEC. 26 T. 31 R. 9W  
SW SW SW  
330' fr SL, 330' fr WL

Total Depth. 4426  
Comm. 5-17-55  
Shot or Treated.  
Contractor.  
Issued. 8-13-55

Comp 5-30-55

County Harper

KANSAS



Elevation. 1611

Production. 346 BOPD

CASING:

9 5/8 261' w/ 150 sx cmt.  
5 1/2 4422' w/ 150 sx cmt.

Figures Indicate Bottom of Formations

red bed & anhydrite	261
shale & anhydrite	1620
shale & lime	1934
shale & anhydrite	2030
shale & shells	2338
shale	2910
shale & shells	3000
shale, lime & shells	3149
shale & lime	3597
lime	4426
Total Depth	

TOPS:

Heebner	3454
Toronto	3489
Douglas	3516
Lansing	3656
Kansas City	3927

DST #1: 4411-21, open 1 hr. 50 min.  
1/2" top, 3/4" btm. choke, gas to  
surf. 5 min. 10 min. gauged 98,000  
CFGPD; 60- 324,000 CFGPD, 80-350,000  
CFGPD, @ 80 min. started to flow mud,  
90 min. started to flow oilst @ 7  
BOPH, flowed 20 min. SI test to pull  
during daylight: rec. 30' muddy oil;  
1120' clean oil, IFP 140#, FFP 480#,  
BHP 1560#/20 min. HP 2300#