

30-31-9W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

PETROLEUM, INC., B. M. HEATH &
Company- J. C. DUDLEY
Farm- Best No. 1

SEC. 30 T. 31 R. 9W
SE SE SE

Total Depth. 4960
Comm. 4-20-55 Comp. 5-12-55
Shot or Treated.
Contractor. Dudley & Heath Drilling Co.
Issued. 9-24-55

County Harper
KANSAS



8 5/8 @ CASING: 264 w/ 250 sx cmt.

Elevation. 1621

Production. Dry

Figures Indicate Bottom of Formations.

not shown	284
red bed	1056
red bed & lime	1503
shaley lime	1654
shale & shells	1825
shale & lime	2292
shale, lime & lime shells	2430
shale & shells	2562
shale	2735
shale & lime streaks	2867
shaley lime & shale	3043
shale & lime	3146
shale	3272
shaley lime	3365
shale	3644
lime & shale	3802
lime	4125
shaley lime & lime	4146
lime	4251
lime & shale streaks	4289
lime	4322
shale & lime	4435
lime	4651
shale & lime	4740
lime	4764
lime & shale	4800
lime	4805
shale & lime	4880
lime	4911
shale & lime	4949
lime	4960
Total Depth	

SCOUT TOPS:

Heebner	3529
Douglas	3580
Lansing	3717
Base KC	4235
Mississippi	4409
Kinderhook	4616
Viola	4720
Simpson	4780
Arbuckle	4920