

31-31-9W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. WALTERS DRILLING CO. ET AL
Farm. Best Unit No. 1

SEC. 31 T. 31 R. 9W
SW NE SE

Total Depth. 4430'
Comm. 8-9-60 Comp. 8-21-60
Shot or Treated.
Contractor. Walters Drlg.
Issued. 10-22-60

County Harper
KANSAS



Elevation. 1541' KB

Production. Dry

CASING:

8 5/8" 202' cem w/170 sx.
2 7/8" 4424' cem w/250 sx.

Figures Indicate Bottom of Formations.

surface soil, shale & shells	205
red rock & shale	700
shale & shells	1400
lime & shale	1690
lime	1835
lime & shale	2505
shale	2725
shale & lime	3737
lime	4174
lime & shale	4372
lime & chert	4390
lime	4430
Total Depth	

TOPS: SCOUT

Heebner	3444
Toronto	3498
Douglas	3522
Douglas Sand	3558
Lansing	3643
Kansas City	3962
Base Kansas City	4180
Mississippi Chert	4352
Mississippi Lime	4386