

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

36-31-9W

Company- O. H. PARKER
Farm- Warren

No. 1

SEC. 36 T. 31 R. 9W
SE NE SE

Total Depth. 4405'

Comm. 4-27-55

Comp. 5-11-55


Shot or Treated.

Contractor. Prime Drlg. Co.

Issued. 6-18-55

County Harper

KANSAS



CASING:

8 5/8"

284' cem w/200 sx

Elevation. 1530' DE

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	30
red bed	285
red bed & shale	1075
shale & shells	1320
Anhydrite	1350
lime & shale	1190
lime & shale strks.	1835
lime & shale	3330
sandy lime & shale	3410
lime & shale	3450
shale, sand & lime	
strks.	3585
lime & shale	3715
lime	4248
lime & shale	4370
lime	4386
chat & lime	4405
Total Depth	RTD

Tops:

Lansing	3622
Kansas City	3878
Mississippi	4381

DRILL STEM TESTS:

- #1 4381-86', open 1 hr., good blow, rec.
2000' gas, 55' slightly oil cut mud and
685' water. 20 min. BHP 1650#, IFP 40#
IFP 385#.
- #2 4397-4405', open 1 hr., good blow, rec.
2200' gas 150' heavy oil and gas cut watery
mud; 500' oil and gas cut water and 560'
water. 20 min. BHP 1670#.