

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kansas


4-32-1W

Company - C. R. A.
Farm - Kate DeTurk "A" No. 2

SEC. 4 T. 32 R. 1W
NW SW SE

Total Depth. 3678
Comm. 7-10-49 Comp. 8-10-49
Shot or Treated. Acidized w/3000 gals.
Contractor. C.R.A.
Issued. 9-24-49

County. Sumner
KANSAS



Elevation. 1231 ft

CASING:
8 5/8" 134' com. w/110 sx.
5 1/2" 3647' com. w/125 sx.

Production. Pumped. 75 bbl. oil &
10 bbls wtr. in 24 hrs.

Figures Indicate Bottom of Formations.

surface soil, clay	13
sand	50
shale & shells	455
lime "broken"-	670
shale	700
lime "broken"-	810
lime sdy	970
lime	1120
lime & shale	2670
sand	2772
lime & shale	2905
shale	2985
shale & shells	3010
lime	3070
lime & shale	3195
lime	3240
lime & shale	3290
shale	3385
shale & shells	3475
shale & lime RTD	3653
lime	3678
Total Depth	

Tops:
Stalnaker 2666
Base Stalnaker 2768
Kansas City 3006
Mississippi 3646