

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

P.E.J. and Mike at it

4-32-1W


SINCLAIR PRAIRIE OIL CO.
Oscar L. DeTurk No. 1.

SEC. 4 T. 32 T. 1W
NWe SW
330' fr WL 330' fr NL

Total Depth. 3676'
Comm. 5-2-37 Comp. 5-29-37
Shot or Treated. 1000 & 2000 Gals.
Contractor. E.B. Shawver
Issued. 8-27-38 Rotary 5649
Cable 3649-3676

AUG 27 1938

County. Sumner



CASING:
13" 330'
7" 3649'
2" tbg. 3666' $\frac{5}{8}$ " 3675'

Elevation.

Production. Pot. 210 Bbls.

Figures Indicate Bottom of Formation.

surface	35
shale	194
shale & shells	270
lime	290
shale	315
lime	318
shale	330
lime	360
shale & shells	450
lime	526
shale & shells	580
lime	650
shale & shells	710
lime	812
shale	896
sdv lime	1020
lime	1110
sdv lime	1133
lime	1175
shale	1390
lime	1420
shale	1450
lime	1500
shale	1575
lime	1610
shale	1687
lime	1785
shale	1860
lime	1875
shale	1940
lime	2100
shale	2114
lime	2345
shale	2470
lime	2490
shale	2675
sdv shale	2808
shale	3020
K.C. lime	3155
shale	3173
lime	3182
shale	3200
lime	3237

shale	3305
lime	3320
shale	3360
lime	3370
shale	3397
lime	3412
shale	3470
sand hrd	3487
shale	3507
lime	3530
shale	3585
shale V.C.	3639
shale	3645
Top Miss. Lime "Chat"	
chat & lime	3676
Total Depth.	

Well was acidized 6-2-37 with 1000 Gals.
6-4-37 swabbed & flowed Est. 150 Bbls.
6-6-37 it was acidized with 2000 Gals.
Production 6-8-37 185 Bbls.
Well would flow awhile after swabbing
then die and would have to swab again.
It was shut down to install OCS pump-
ing unit.
First 24 hrs production after pumping
unit was installed was 210 Bbls.