

4-32-1 W

WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - C. R. A.
Farm - O. L. DeTurk

No. 5

SEC. 4 T. 32 R. 1W
SE SE SW

Total Depth. 3680

Comm. 6-26-49

Comp. 8-20-49


County. Sumner

KANSAS

Shot or Treated. Acidized w/6000 gals. total Shot w/20 qts 3657-57

Contractor. C.R.A.

Issued. 9-24-49



CASING:

10 3/4" 157' con. w/110 sx.

5 1/2" 3643' con. w/80 sx.

Elevation. 1222 *Ind*

Production. Pmpd. 43 bbls oil
2 bblw water 1st 24 hrs.

Figures indicate Bottom of Formations.

surface soil	14
sand	45
shale & shells	140
shaly shells	160
shale	225
shale & lime	360
lime sdy	480
lime	700
sand & lime	880
lime	1205
lime & shale	1305
lime	1440
shale & lime	1715
shale & shells	1775
lime sft & shale	2000
lime	2142
shale & shells	2320
lime brkn	2470
shale	2570
shale & shells	2657
sand	2665
Stalnaker sand	2770
shale	2890
shale & shells	2975
shale	3009
K. C. lime	3075
lime & shale	3140
lime	3215
lime & shale	3637
shale	3646
Miss. chat	3653
chert	3667
chert & dolo.	3680
Total Depth	

Tops:

Stalnaker	2659
Base Stalnaker	2766
Kansas City	3005
Mississippi	3642