

OIL CORP. & DEWAR OIL CO.
rock No. 1.

STELBAR OIL CORP.
E.A. ROTH ROCK No. 1


SEC. 4 T. 32 R. 1W.
NW NE NW

4-32-1W

County Sumner.

Total Depth. 3699
Comm. 12-4-36 Comp. 12-31-36
Shot or Treated.
Contractor. E.B. Shawver.
Issued. 1-30-37

JAN 30 1937



CASING.

10" 331' 65/8" 3646'

Elevation.

Production. Pot. 1297 B.

Figures Indicate Bottom of Formations.

shale and shells	120	shale	2375
salt and shells	220	lime broken	2385
shale	230	shale	2405
lime	235	lime	2420
shale and shells	328	shale	2440
lime	337	lime broken	2485
shale and shells	355	shale	2490
lime broken	725	lime	2510
shale	740	shale	2542
lime broken	800	lime broken	2560
shale and shells	825	shale	2653
lime broken	925	lime	2657
shale and shells	935	shale	2670
lime	1008	shy lime	2760
shale	1020	shale	2770
lime	1124	shy shale	2790
shale	1134	shale	3016
lime	1165	K.C. lime	3262
shale	1172	shale	3290
lime broken	1218	lime	3332
shale	1268	shale	3446
lime broken	1302	lime	3457
shale	1333	shale	3531
lime	1378	lime	3535
shale	1385	shale	3643
lime broken	1395	chat and lime	3699
shale	1410	Total Depth.	
lime	1465		
shale	1485	Prod. 1st 24 hours swabbed 7 bbls	
lime shells	1534	per hour nat.	
shale and shells	1575	Detail of shot.	
lime broken	1595	Acidized 1-3-37 1000 gal treatment.	
shale	1630	Reacidized 1-5-37 with 3000 gal	
lime shells	1670	treatment.	
sticky shale	1735		
lime broken	1804	State Potential completed	
shale	1842	1-9-37 1297 bbls in 24 hours.	
lime	1850		
shale	1865		
lime broken	1900		
shale	1940		
lime shells	1962		
shale	1998		
lime	2180		
shale	2190		
lime	2332		
shale	2342		
lime	2365		