

THE TEXAS CO.
Ellis Carr No. 1.


SEC. 5 T. 32 R. 1W
NEo NE
Approx. 330' fr N & EL NE $\frac{1}{4}$
5-32-1W
County. Sumner

Total Depth. 3670'
Comm. 10-9-36 Comp. 12-2-36
Shot or Treated. 1000 Gals. & 2000 Gals.
Contractor. Helmerich & Payne, Inc.
Issued. 1-16-37 Rotary O-3624'
Cable 3624-70'

CASING:

12 $\frac{1}{2}$ " 332'
8 $\frac{1}{4}$ " 3652'

JAN 16 1937



Elevation.

Production. Pot. 825 B.
after acid.

Figures Indicate Bottom of Formations.

clay & shale	75
shale & lime shells	360
lime hrd	500
lime & shale	670
lime	700
lime & shale	790
shale	805
lime hrd	835
lime & shale	940
lime	996
lime	1578
shale	1650
lime	1670
shale & lime	1809
lime	1890
lime & shale	1935
lime	2184
lime hrd	2220
lime	2318
lime & shale	2355
lime	2462
lime & shale	2530
shale	2702
shale & lime sdy	2780
shale	2882
shale & shells	2899
shale	3008
shale & lime	3050
lime	3131
shale	3184
lime & shale	3221
lime	3252
lime & shale	3304
shale	3624
lime	3626
chat Top	3670
Total Depth.	

Flowing 265 Bbls. 1st 24 hrs.
after being acidized with 1000
gallons.

Second test taken after being
acidized with an additional
2000 gallons was 825 bbls. oil Pot.