


THE TEXAS COMPANY.
E. Carr No. 2.

5-32-10
SEC. 5 T. 32 R. 1W
NW NE NE
Approx. 330' fr NL 990' fr EL
NE $\frac{1}{4}$

County. Sumner

Total Depth. 3682'6"
Comm. 12-14-36 Comp. 1-19-37
Shot or Treated.
Contractor. Springrose Drlg.Co.
Issued. 2-27-37

FEB 27 1937



CASING: Rotary 3636
Cable 3682'6

12 $\frac{1}{2}$ " 345'
8 $\frac{1}{4}$ " 3636'

Elevation.

Production. Flow 1040 B.
1st 24 hrs.

Figures Indicate Bottom of Formations.

surface hole	65
shale & shells	150
surface shale & shells	340
lime	345
shale & lime shells	553
lime & shale	620
brkn lime	785
shale & lime shells	820
lime & shale	920
lime	945
shale	985
lime	1010
shale & lime	1030
lime	1045
lime & brkn shale	1120
brkn lime	1200
shale	1230
shale & shells	1310
shale	1385
sand	1409
shale & shells	1426
shale	1630
brkn lime	1650
shale	1717
shale & lime shells	1858
shale & lime	1931
shale	2020
brkn lime	2042
shale & lime brkn	2106
shale & lime	2189
lime	2310
shale	2327
lime	2350
shale	2410
lime	2450
shale & lime shells	2475
shale & lime	2540
lime	2577
lime & shale	2630
shale	2670
shale & sand	2755
shale & lime	2800
sticky shale	2830

shale	3655
chat	3658
lime	3682 $\frac{1}{2}$
Total Depth.	

Flowing 1040 B. 1st 24 hrs.
This test was taken after the
well had been acidized.

shale	3036
lime	3234
lime & shale black hrd	3284
shale	3315
shale & lime	3350
sticky shale	3380
shale & lime shells	3420
shale	3460
sticky shale	3480
brkn lime	3495
shale	3532
shale & lime shells	3650