

5-32-1 W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - STELBER OIL CORP.  
Farm - Cora Stone No. 2

SEC. 5 T. 32 R. 1 W  
SW NW SW

Total Depth. 3683'  
Comm. 3-5-47 Comp. 3-31-47  
Shot or Treated.  
Contractor. E. B. Shawver  
Issued. 6-21-47

County. Sumner  
KANSAS



Elevation. 1206.5 ft.  
1203.0 ft.

Production. Est. 5 BOPD

CASING:

8" 139' Cem. w/40 sx.  
5 1/2" OD 3640' Cem. w/40 sx.

Figures Indicate Bottom of Formations.

surface soil	25
gravel	35
shale & shells	115
lime brkn	145
shale & shells	1620
lime	1727
shale	2082
lime	2275
shale	2685
shale sdy	2759
shale	3012
K. C. lime	3070
lime	3270
shale	3639
chat	3683
Total Depth.	

Tops:

Kansas City	3012
Chat	3639

dolomite med por., no sat. 3640-51'  
 dolomite med. por., lgt stain 3651-57'  
 dolomite med por. cherty, lgt stain 3657-67'  
 dolomite cherty, tighter, no sat. 3667-79'  
 dolomite cherty, tight, no sat. 3679-83'

Well acidized w/5000 gals. treatment.

I.P. Very little oil, some wtr.,  
Well made about 5 BOPD after acid,  
wtr. inc.