

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas


18-32-1W

Company- STEELBAR OIL CORP.
Farm- O'Hara No. 5

SEC. 18 T. 32 R. 1W
NW SW NW

Total Depth. 3766'
Comm. 6-15-57 Comp. 6-25-57
Shot or Treated.
Contractor. Prairie Oil & Gas Co.
Issued. 12-7-57

County Sumner
KANSAS



Elevation. 1270' DF

Production. 29 BOPD w/water

CASING:

8 5/8" 412' cem w/250 sx.
5 1/2" 3759' cem w/250 sx.

Figures indicate Bottom of Formations.

surface clay	30
broken lime & shale	108
broken lime	261
shale & shells	2747
Stalnaker sand	2855
shale	3095
K.C. lime	3365
shale	3375
shale & lime	3736
Miss. chert	3745
Miss. lime - cored	3766 RTD
Total Depth	

TOPS: ELECTRIC

Stalnaker	2748
Kansas City	3095
Base Kansas City	3355
Mississippi Chert	3730
Mississippi Lime	3743

Perforated 3284-3294.

Perforated 3294-3300.

Acidized with 2000 gal. Type J.

State Potential 8-19-57, 29 BOPD with water.

Pumping Test: 50 BO, 2 BW per day.