

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION COMPANY
 Farm- Champ Unit No. 1

SEC. 2 T. 32 R. 10W
 NE SW SW

Total Depth. 4475
 Comm. 4-27-57 Comp. 5-28-57
 Shot or Treated.
 Contractor. Herndon Drlg Co.
 Issued. 8-24-57

County Barber
 KANSAS



CASING:

8 5/8" 225' cem w/175 sx.
 5 1/2" 4475' cem w/100 sx.

Elevation. 1524

Production Pot. 15,000,000 CFGPD

Figures indicate Bottom of Formations.

surface hole	225
shale, shells	1450
shale, lime	1745
lime	1935
lime, shale	2095
lime	2100
lime, shale	3600
lime	4475
Total Depth	

Tops:

Heebner (Scout)	3503
Toronto (")	3537
Douglas	3564
Douglas sand	3638
Lansing-K. C.	3678
Base Kansas City	4098
Miss.	4350

Core #1 4350-4353
 #2 4353-4364
 #3 4364-4373
 #4 4373-4382
 #5 4382-4400
 #6 4400-4415
 #7 4415-4435

DST #1 4352-4415 Op. 40'
 ISI 30", FST 30",
 Gauged 1,250,000 CFG in 5".
 " 2,420,000 " " 30"
 " 2,630,000 " " 40"

Recovered 290' GCM & 30' GCWM-ISIP
 1716#, FSIP 1642#, FP 428-519#.

GRN Log- PBTB - 4442- Perf. Miss.
 4353-83-120 \$ - NS
 Re Perf. Miss. 4350-73- 80 \$- NS
 500 Acid.

1st hr 430 MCFPD

13th hr 847 "

Frac-Miss. w/30,000 Acid. petro frac
 w/30,000 #.