

*End*  
\* SIDE ONE

## AFFIDAVIT OF COMPLETION FORM

13-32 SEP 10 1982  
(REV) ACO-1

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).  
KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Rains & Williamson Oil Co., Inc.

API NO. 15-007-21,363

ADDRESS 435 Page Court, 220 West Douglas

COUNTY Barber

Wichita, Kansas 67202

FIELD Sharon

\*\*CONTACT PERSON Juanita Green

PROD. FORMATION Mississippian

PHONE 265-9686

LEASE McDaniel-Johnson

PURCHASER Clear Creek, Inc.

WELL NO. 1

ADDRESS 818 Century Plaza Building

WELL LOCATION 330' S. of NW NW SE

Wichita, Kansas 67202

2310 Ft. from East Line and

DRILLING Rains & Williamson Oil Co., Inc.

1980 Ft. from South Line of

CONTRACTOR

the SEC. 13 TWP. 32S RGE. 10W

Wichita, Kansas 67202

PLUGGING *State Geological Survey*

WELL PLAT

CONTRACTOR

ADDRESS

TOTAL DEPTH 4396' PBTD

KCC

SPUD DATE 1-25-82 DATE COMPLETED 2-5-82

ELEV: GR 1480 DF  KB 1489

KGS

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

(Office Use)

RECEIVED

STATE CORPORATION COMMISSION

JUN 16 1982

CONSERVATION DIVISION

Wichita Kansas

Amount of surface pipe set and cemented 249' w/175 sx. DV Tool Used?

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS, I,

Wilson Rains OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR)(OF) Rains & Williamson Oil Co., Inc.

OPERATOR OF THE McDaniel-Johnson LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF April, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

## SIDE TWO

## WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 30 (60) 60 (60). Rec. 5' Slightly GWM, 60' WM. FP's 96053, 96-43. IBHP 420, FBHP 942.	4334	4379	ELECTRIC LOG TOPS	13-32-10w
DST #2 30 (60) 60 (60). Rec. 165' Slightly GCM. FP's 236-225, 236-193. IBHP 1334, FBHP 1324.	4378	4389	Heebner Lansing KC B/KC Mississippi L.T.D.	3435 (-1946) 3653 (-2164) 3937 (-2448) 4173 (-2684) 4362 (-2873) 4396 (-2907)
DST #3 30 (60) 60 (60). Rec. 500' Clean gassy oil. FP's 527-527, 580-612. IBHP 1335, FBHP 1345.	4386	4396		

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				Gravity
4-11-82	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 10 bbls.	Gas MCF	Water %	Gas-oil ratio bbls.	CFPB
Disposition of gas (vented, used on lease or sold)	Perforations				

## Report of all strings set—surface, intermediate, production, etc. Casing Record (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 <sup>1</sup> / <sub>4</sub> "	8 5/8"	20#	249'	Class H.	175 sx.	2% gel, 3% cc.
Production	7 7/8"	4 1/2"	10 <sup>1</sup> / <sub>2</sub> #	4392'	RSC Dowell	120 sx.	

## LINER RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

## TUBING RECORD

Size	Setting depth	Packer set at			

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 13 T. 32S R. 10W

WELL NAME: McDaniel-Johnson #1

LOC. 330' S. of NW NW SE

COUNTY: Barber

RIG NO. #3

TOTAL DEPTH 4396'

ELEVATION 1480 GL 1489 KB

COMMENCED: 1-25-82

COMPLETED: 2-5-82

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 249' w/175 sx. Class H, 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4392' w/120 sx. RSC Dowell.

LOG

(Figures Indicate Bottom of Formations)

Redbed	750
Redbed & Shale	1574
Shale	3390
Lime & Shale	3735
Lime	4396
<u>ROTARY TOTAL DEPTH</u>	<u>4396</u>

RECEIVED  
STATE CORPORATION COMMISSIONER  
FEB 10 1982  
CONSERVATION DIVISION  
WICHITA, KANSAS

STATE OF Kansas) SS:  
COUNTY OF Sedgwick)

J. Wilson Rains, President

of Rains & Williamson Oil Co., Inc.