

13-32-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DURBIN BOND & JOHN O. FARMER
Farm- McKeever No. 2

SEC. 13 T. 32 R. 10W
C E/2 NW SE

Total Depth. 4384'
Comm. 10-27-57 Comp. 11-10-57
Shot or Treated.
Contractor. D & M Drlg.
Issued. 8-16-58

County Barber
KANSAS



CASING:
8 5/8" 258' cem w/180 sx.
5 1/2" 4383' cem w/100 sx.

Elevation. 1479' KB

Production. 27 BOPD

Figures Indicate Bottom of Formations.

redbed strks & sand	100
redbed	258
redbed & shale	500
shale & shells	1175
Anhydrite	1195
shale, shells & Anhy. streaks	1500
shale & lime	1525
broken lime	1670
lime & shale	2370
shale w/lime streaks	2725
lime & shale	3525
shale & sand	3630
lime & shale	3725
lime	3849
lime & shale	3900
lime	4012
lime & shale	4052
lime	4102
lime & shale	4367
Mississippi lime	4372
chert	4384
Total Depth	

TOPS: SCOUT
Anhydrite 1175
Mississippi 4359

Perforations: 4374' to 4378'

Dowell frac w/1500# sand & 1500 gal.
acid