

3/27/82
13-32-10W KCC 81
(REV) ACO-1

Handwritten initials/signature

SIDE ONE

AFFIDAVIT OF COMPLETION FORM

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Rains & Williamson Oil Co., Inc.

API NO. 15-007-21,364

ADDRESS 435 Page Court, 220 West Douglas

COUNTY Barber

Wichita, Kansas 67202

FIELD Wildcat SHARON

**CONTACT PERSON Juanita Green

PROD. FORMATION Mississippian

PHONE 265-9686

LEASE Schreiner Farms

PURCHASER Clear Creek, Inc.

WELL NO. 1

ADDRESS 818 Century Plaza Building

WELL LOCATION SE SW NW

Wichita, Kansas 67202

990 Ft. from North Line and

DRILLING Rains & Williamson Oil Co., Inc.

2310 Ft. from West Line of


CONTRACTOR ADDRESS 435 Page Court, 220 West Douglas

the SEC. 13 TWP. 32S RGE. 10W

Wichita, Kansas 67202

WELL PLAT

PLUGGING CONTRACTOR ADDRESS



KCC
KGS
(Office Use)

TOTAL DEPTH 4404' PBD

SPUD DATE 1-12-82 DATE COMPLETED 3-27-82

ELEV: GR 1490 DF KB 1499

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 248' w/225 sx. DV Tool Used?

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS, I,

Wilson Rains OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR)(OF) Rains & Williamson Oil Co., Inc.

OPERATOR OF THE Schreiner Farms LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

WAS COMPLETED AS OF THE 27th DAY OF March, 1982, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

RECEIVED STATE CORPORATION

13-32-10w

SIDE TWO

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 30 (60) 60 (60). Rec. 70' muddy water w/oil spots. FP's 42-42, 95-95. IBHP 1047, FBHP 1047.	4102	4130	ELECTRIC LOG TOPS	
			Heebner	3450 (-1951)
			1st Doug. Sd.	3498 (-1999)
			2nd Doug. Sd.	3559 (-2060)
			Lansing	3646 (-2145)
			KC	3948 (-2449)
DST #2 open 30 min. Rec. 805' clean gassy cut oil. GTS 3". Flowed in 18". FP's 749-945. IBHP 1395. Shut in all night.	4362	4404	Stark	4104 (-2605)
			B/KC	4182 (-2683)
			Miss.	4396 (-2897)
			Miss. Poros.	4398 (-2899)
			L.T.D.	4401 (-2902)

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated	
None			
Date of first production 3-27-82		Producing method (flowing, pumping, gas lift, etc.) Pumping	
Gravity			
RATE OF PRODUCTION PER 24 HOURS	Oil 50 bbls.	Gas - MCF	Water 20 % bbls.
Disposition of gas (vented, used on lease or sold)		Perforations	

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	20#	248'	Class H.	225 sx.	2% gel, 3% cc.
Production	7 7/8"	4 1/2"	10 1/2#	4399'	60-40 poz.	150 sx.	10% salt, 3% CFR-2.

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			None		
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	4402'	-			

P1

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 13 T. 32S R. 10W

WELL NAME: Schreiner Farms #1

LOC. SE SW NW

COUNTY: Barber

RIG NO. #3

TOTAL DEPTH 4404'

ELEVATION 1490 GL 1499 KB

COMMENCED: 1-12-82

COMPLETED: 1-22-82

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 248' w/225 sx. Class H, 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4399' w/150 sx. 60/40 poz., 10% salt, 3% CFR2.

LOG

(Figures Indicate Bottom of Formations)

Redbed	620
Shale	3135
Shale & Lime	3345
Lime & Shale	4404
<u>ROTARY TOTAL DEPTH</u>	<u>4404</u>

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1982

CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President

of

Rains & Williamson Oil Co., Inc.