

14-32-10W ✓


~~WELL LOG BUREAU~~ KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- KWB OIL PROPERTIES MANAGEMENT, INC.  
Farm- Lies No. 1

SEC. 14 T. 32 R. 10W  
C NE SE

Total Depth. 4402'  
Comm. 4-22-65 Comp. 5-2-65  
Shot or Treated.  
Contractor. Sierra Pet. Co., Inc.  
Issued. 11-27-65

County Barber  
KANSAS



Elevation. 1477' KB

Production. 125 BOPD, NW

Figures Indicate Bottom of Formations.

CASING:

8 5/8"	208'
5 1/2"	4399'
red bed	450
shale, shells	980
shale, s lt	1180
shale, shells	1300
shale, lime	3558
sand	3636
lime, shale	3660
lime	4385
lime, chert	4402
Total Depth	

TOPS: SCOUT

Elgin zone	3247
Elgin sand	3301
Heebner	3433
Toronto	3448
Douglas shale	3480
Douglas sand	3554
Lansing	3634
Kansas City	3934
B/Kansas City	4142
Marmaton'	4216
Mississippi	4375