

SIDE TWO

Operator Name Attica Gas Venture Corp. Lease Name Werner Well # 2-85

21 32 10 East
 West County Barber

Estimated Production Per 24 Hours	Oil Bbls	Gas 200 MCF	Water -0- Bbls	Gas-Oil Ratio CFPB	Gravity
-----------------------------------	-------------	----------------	-------------------	-----------------------	---------

METHOD OF COMPLETION Production Interval

Disposition of gas: Vented Open Hole Perforation
 Sold Other (Specify) 4394-4397

Drill Stem Tests Taken Yes No
Samples Sent to Geological Survey Yes No
Cores Taken Yes No

Log Sample

Log TD 4690 - Driller TD 4700 (log correlates 8' higher)
DST#1 4397-4442 GT33", Gal, 5559 MCF in 10", 1,760 MCF/GPD, IF327-337#/30", FBHP 1276#/145" (test discontinued - mechanical problem).

DST#2 4686-4700 Rec 340' GIP, 20' OCGWM, 60' WM, 120' SW IF 97-97#/20", ISIP 1382#/30", FF 69-111#/60" IH 2429# FH 2345# BHT 125 °F .

Ran GT gun dual ind. - Neutron density porosity logs.

Name	Top	Bottom
	0	915
	915	1630
Chase Group	1630	2442
Indian Cave (Admire)	2467	2491
	2491	2672
Tarkio SS	2672	2684
	2684	3247
Queenhill Sh.	3247	3252
	3252	3460
	3460	3464
Heebner Sl	3464	3662
Lansing	3662	4340
Cherokee Shade	4340	4344
	4344	4382
Mississippi	4382	4392
	4392	4398
	4398	4594
Kinderhook Sh.	4594	4644
Chattanooga Sh	4644	4682

CASING RECORD New Used Viola 4682 4690
Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	24#	256	Common	175	2% Gel 3% CaCl
Production	7 7/8"	5 1/2"	14#	4509	Common	135	35 sax scavenger slurry - + Thixo-tropic additives

PERFORATION RECORD Acid, Fracture, Shot, Cement Squeeze Record

Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Depth
4	4394 - 4397	1000 Gal 15% HCl + clay stabilizers & iron sequestrants	

TUBING RECORD Size 2 3/8 Set At 4411 KB Packer at _____ Liner Run Yes No

Date of First Production _____ Producing Method Flowing Pumping Gas Lift Other (explain).....
Waiting on line _____