

15-007-20387

State Geological Survey
KANSAS DRILLERS LOG
WICHITA BRANCH

S. 22 T. 32 R. 10W
50' E/NW NE NW
Loc. _____

API No. 15 — 007 — 20,387
County Number

County Barber

Operator
Vincent Oil Corp.

Address
901 Union Center Wichita, Kansas 67202

Well No. #1 Lease Name Eck

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Graves Drilling Co., Inc. Geologist Robert Hammond

Spud Date Feb. 3, 1976 Total Depth 4400 P.B.T.D.

Date Completed 12-12-76 Oil Purchaser Koch Oil

640 Acres
N

Locate well correctly

Elev.: Gr. 1459

DF _____ KB 1470'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface casing	12 1/4"	8-5/8"	28#	239'	Common	235	2% Gel 3% CC
Production		5 1/2"		bottom			

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 6044.

erator

Vincent Oil Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil and Gas

Well No.
#1

Lease Name
Eck

S 22 T 32 R 10 ^E/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Topeka	3116
			Heebner	3448
			Lansing	3645
			Stark Shale	4089
			B/Kansas City	4141
			Cherokee Shale	4313
			Eros. Miss.	4361
			Mississippi Chert	4370
			Total Depth	4400
<p>Drill Stem Test #1 4345-4400 - 30-45-60-45 - Gas to surface in 2 min., gauged 847 MCFG at end of 1st opening. Gauged 1,000 MCFG in 5 min. on 2nd opening and declined to 411 MCFG in 45 min. Then heavy mud spray with some oil at end of 2nd opening. Rec. 1260 ft. gassy oil, 120 ft. oil and gas cut mud. IFP 274-288#, ISIP 1454#, FFP 263-430#, FSIP 1361#. Ran 5½" casing on bottom.</p>				
<p>USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.</p>				

Date Received

Signature

Title

Date

22-32-10W

State Geological Survey
WICHITA, BRANCH

ROTARY DRILLERS' LOG

OPERATOR: Vincent Oil Corporation DRILLING COMMENCED: Feb. 3, 1976
 901 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: Feb. 13, 1976
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 6 Jts. 239' of used 8-5/8" LOCATION: Eck No. 1
 cemented with 235 sacks; 50' E of NW NE NW
 136 Jts. 4400' of used 5-1/2" Section 22-32S-10W
 cemented with 100 sacks Barber County, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 18 1976
 CONSERVATION DIVISION
 Wichita, Kansas

0 - 400	Sand & shale
400 - 1634	Shale & sand
1634 - 2133	Shale & shells
2133 - 2665	Shale
2665 - 2875	Shale with lime
2875 - 4155	Shale & lime
4155 - 4340	Lime & shale
4340 - 4400	Lime with shale
4400	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves*
 President

STATE OF KANSAS)
)
 WICK COUNTY)

SS: